

**DOCUMENT 00 90 00
ADDENDUM**

ADDENDUM NO. [1] Date: March 28, 2019

**RE: WITC – RICE LAKE CAMPUS
MEP/ZONE 4 RENOVATIONS REBID
1900 COLLEGE DRIVE
RICE LAKE, WI
HSR PROJECT NO. 18043-3**

**FROM: HSR Associates, Inc
100 Milwaukee Street
La Crosse, WI 54603
(608) 784-1830**

To: Prospective Bidders

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated February 2019. Acknowledge receipt of this Addendum in the space provided on the bid form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of three (2) pages AND (1) Pre-bid attendance.

CHANGES TO BIDDING REQUIREMENTS AND CONDITIONS OF THE CONTRACT:

1. See 3-27-19 Pre-bid sign-in sheet attached hereto. Note that general contractors who had attended the first pre-bid conference were not required to attend this one.
2. Section 00 21 13 INSTRUCTIONS TO BIDDERS:
 - a. 4.3 Submission of Bids: Emailed or Faxed bid WILL NOT be accepted.

GENERAL REQUIREMENTS:

3. Section 01 10 000 SUMMARY
 - a. At 1.10 (B) Line shall be changed to read: DATE OF SUBSTANTIAL COMPLETION OF ALL WORK: 12 AUGUST, 2019.
4. Section 01 23 00 ALTERNATES
 - a. At 1.05 (B) Add after Area C “*and Area E.*”

CHANGES TO SPECIFICATIONS:

5. Section 08 43 13 ALUMINUM FRAMED STOREFRONTS
 - a. ELIMINATE 2.06 (B). All finishes shall be anodized.
6. Section 09 84 30 SOUND ABSORBING WALL AND CEILING UNITS
 - a. Remove section from Contract Documents. Acoustical panel Work shall be removed from the project.

7. Section 09 67 00 FLUID APPLIED FLOORING

- a. 2.01, A, 2: Last item in system description shall read "Eco-HTS 100"

CHANGES TO DRAWINGS:

8. Sheet A201 EXTERIOR SITE PHOTOS

- a. Replace all notes reading "(ALT BID) REMOVE EXISTING METAL ROOF EDGE/CAP FLASHING AS NEEDED FOR EIFS PANEL REPLACEMENT & REINSTALLATION" to:
"(ALT BID) REMOVE AND REINSTALL EXISTING METAL ROOF EDGE/CAP FLASHING AS NEEDED FOR EIFS REFINISHING WORK."

9. Sheet A601 DOOR SCHEDULE

- a. At detail 1: At window "C" change GLT-14 to GLT-13.

10. Sheet P101B ABOVE GRADE PLUMBING PLAN – AREA B

- a. Note: At Janitor Room 192, replace existing mop sink faucet and extensions with a "Chicago model #911-CP" or approved equal.

END OF DOCUMENT 00 90 00

3-27-2019

<u>NAME</u>	<u>COMPANY</u>	<u>E-mail</u>
Kevin Berg	Market & Johnson	Kberg@market-johnson.com
Greg Sachaus	Certified Inc	greg@certified-planting-landscaping.com
Josh Gardow	Rhom Construction	jjgardow@rhomconstruction.com
Tyler Gosso	Thomas-Grace	tyler.gosso@thomas-grace.com
Scott Kupferschmidt	WITC	SCOTT.KUPFERSCHMIDT@WITC.EDU
Kristi Foust	WITC	kristi.foust@wiz.edu