

DOCUMENT 00 90 00

ADDENDUM

ADDENDUM NO. [1]

Date: May 9, 2019

**RE: WESTERN TECHNICAL COLLEGE
ADMIN CENTER
WELLNESS CENTER MEN'S SHOWER
111 SEVENTH STREET NORTH
LA CROSSE, WISCONSIN 54601
HSR PROJECT NO. 19015**

FROM: HSR Associates, Inc
100 Milwaukee Street
La Crosse, WI 54603
(608) 784-1830

To: Prospective Bidders

This addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated April 2019. Acknowledge receipt of this Addendum in the space provided on the bid form. Failure to do so may subject the Bidder to disqualification.

This Addendum consists of [1] page, [1] specification section, and [1] 30 x 42 drawing.

CHANGES TO SPECIFICATIONS:

1. Section 10 21 13.19 PLASTIC TOILET PARTITIONS
 - a. 2.03, B: Headrails shall have curtain track and curtain carriers. Curtain specified in Section 10 28 00.
2. Section 10 21 23 CUBICLE CURTAINS AND TRACKS
 - a. Section attached hereto as part of Contract Documents.
3. Section 10 28 00 TOILET, BATH AND LAUNDRY ACCESSORIES
 - a. 2.04, C, 1: Delete rod and provide curtain only. Carriers provided by other sections.

CHANGES TO DRAWINGS

4. Sheet A100 DEMOLITION AND REMODEL FLOOR PLANS 30 x 42 drawing attached hereto
 - a. Revisions clouded on Drawing
 - b. Add headrails with curtain track and curtain carriers to shower partitions at north stalls
 - c. Accessory Schedule
 - i. Add HR headrails with curtain track and curtain carriers for shower partitions
 - ii. Change single robe hook to double.
 - d. Southwest corner shower stall:
 - i. Remove shower rod and install ceiling curtain track with carriers.
 - ii. Remove towel bar and add two additional coat hooks.
 - e. Install dust partition and door as noted.
 - f. Provide floor protection at construction traffic areas. See Section 01 70 00 as well.

END OF DOCUMENT 00 90 00

Page Intentionally Left Blank

SECTION 10 21 23
CUBICLE CURTAINS AND TRACK

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. Surface mounted overhead curtain track and guides.

1.02 SUBMITTALS

- A. See Section 01 30 00 - Administrative Requirements, for submittal procedures.

1.03 DELIVERY, STORAGE, AND HANDLING

- A. Accept curtain materials on site and inspect for damage.
- B. Store curtain materials on site and deliver to Owner for installation when requested.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Cubicle Curtain Tracks:
 - 1. Econo Cube System by InPro Corporation, www.inprocorp.com: Comparable by:
 - 2. Kirsch.
 - 3. A. R. Nelson Co: www.arnelson.com.
 - 4. General Cubicle Co., Inc: www.generalcubicle.com.
 - 5. Imperial Fastener Co., Inc: www.imperialfastener.com.
 - 6. Substitutions: See Section 01 60 00 - Product Requirements.

2.02 TRACKS AND TRACK COMPONENTS

- A. Tracks: Extruded aluminum sections; one piece per track run.
 - 1. Profile: Channel.
 - 2. Mounting: Surface.
 - 3. Track End Stop: To fit track section.
 - 4. Finish on Exposed Surfaces: Clear anodized.
- B. Curtain Carriers: Nylon rollers, size and type compatible with track; designed to eliminate bind when curtain is pulled; fitted to curtain to prevent accidental curtain removal.
- C. Wand: Plastic, attached to lead carrier, for pull-to-close action.
- D. Installation Accessories: Types required for specified mounting method and substrate conditions.

PART 3 EXECUTION

3.01 EXAMINATION

- A. Verify that surfaces are ready to receive work of this Section.
- B. Verify that field measurements are as indicated.

3.02 INSTALLATION

- A. Install curtain track to be secure, rigid, and true to ceiling line.
- B. Secure track to ceiling system.
- C. Install end cap and stop device.

END OF SECTION

